

HBSP - Skills and Training Framework



Plaster & Dry-liners and Plaster & Dry-liners Supervisor

The information on this spreadsheet contains the agreed modules across the Home Building Sector for either an Plasters and Dry-liners. Subsequent tabs will give a more detailed overview of course content and key objectives along with, where available, links to samples of full course programmes. Over the coming months and in line with the work on CITB Grant reform and National Training Standards the relevant key information, where available will be added. Its primary aim is to help with standardising, understanding, developing, deployment and the tracking of people and their skills. The information within this and all associated Skills Matrices for Home Building should be used as a **minimum** standard across the sector.

Module	Unit of Training	P&DL	P&DL Superv
Regulatory Environment & Standards			
Health, Safety & Environment	SSSTS / IOSH or equivalent		y
	Hazards & Controls	y	y
	Health and safety awareness for operatives	y	y
Construction Process			
	Defects Prevention Introduction	y	y
Qualification	L2/equivalents		
	VA Level 2 or Level 3 in Dry Lining/Plastering		
	Apprenticeship Dry Lining/Plastering		
	Diploma in Dry Lining/Plastering	X	
Site & Project Planning			
Technical Drawings	Understanding drawings & specs	y	y
IT Skills	Software & hardware skills		y
Project Management	Compiling site programmes		y
BIM	Awareness (optional)		y
Technical Drawings	Understanding drawings & specs		y
Commercial Awareness	Costing & Finance		y
Management			
Leadership skills, culture & behaviours	Managing teams		y
	Managing Meetings		y
	Assertiveness		y
	Customer Service		y
	Managing Performance		y
People Management			
	Roles & Responsibilities		y
	Employment law		y
	Conflict resolutions		y
	Motivating others		y

Minimum Productivity Requirements

Based on a typical 3-bedroom detached home with single garage, en-suite, 1 family bathroom, 1 separate toilet, fitted kitchen and utility area

The dry-lining phase for walls & ceilings includes for screw fix and/or dot & dab, load out of boarding to each floor level:

2 Dry-liners - 6 days.

Plaster skim:

2 Plasterers - 8 days.



In conjunction with

